



NOTES:

- 10" GATE VALVE BOX TOP SECTION WITH DROP LID (SEWER) SHALL BE INSTALLED WITH ALL CLEANOUTS. 1" BELOW FINISHED GRADE.
- 4" PVC SCHEDULE 40 CLEANOUT RISER WITH REMOVABLE CAP 4"-6" BELOW FINISH GRADE.
- ENCLOSE LONG SWEEP BEND OR COMBINATION WYE IN 4" CONCRETE AS SHOWN



LAST REVISION
NOVEMBER 2014

SANITARY SEWER CLEANOUT

CITY OF MAPLE GROVE ENGINEERING
& PUBLIC WORKS DEPARTMENTS

STANDARD
PLATE #
SS-3