



NOTES:

- STRUCTURE SHALL BE REINFORCED PRECAST CONCRETE
- GRATING SHALL BE HOT DIPPED GALVANIZED AFTER FABRICATION
- ALL ANCHOR BOLTS SHALL BE $\frac{1}{2}$ ϕ STAINLESS STEEL EXP. ANCHORS W/4" MINIMUM EMBEDMENT
- MAXIMUM SIZE PIPE TO BE 18"

